

**कार्यालय यू0पी0कोआपरेटिव फेडरेशन लि0
32- स्टेशन रोड लखनऊ।**

कार्यालय यू0पी0 कोआपरेटिव फेडरेशन लि0 लखनऊ की ओर से पी0सी0एफ0 32 स्टेशन रोड लखनऊ परिसर में एक नये नलकूप क्षमता 8"x 6" का निर्माण कार्य किया जाना है निविदा का विवरण निम्नवत है:-

क्र0 सं0	कार्य का विवरण	अनुमानित लागत लाख में	निविदा फार्म का मूल्य रु0 में	धरोहर धनराशि रु0 में	पूर्णता अवधि
1	पी0सी0एफ0 मुख्यालय परिसर में नये नलकूप क्षमता 8"x 6" का निर्माण, संस्थापन, पम्पिंग प्लांट का अधिष्ठान, पिलर, गर्डर का निर्माण, राइजिंग कनेक्शन एवं क्लोरोनेटिंग प्लांट का अधिष्ठान का निर्माण कार्य	रु0 19.49	रु0 2000.00 + पी0एस0टी 18 प्रतिशत कुल रु0 2360.00	रु0 39,000.00	तीन माह


धरोहर धनराशि एवम् निविदा मूल्य डिमाण्ड ड्राफ्ट यू0पी0 कोआपरेटिव फेडरेशन लि0, पेबिल एट लखनऊ के पक्ष में भौतिक रूप से पी0सी0एफ0 मुख्यालय 32-स्टेशन रोड लखनऊ के पॉचवे तल पर महाप्रबन्धक (निर्माण) के कार्यालय कक्ष में 6.09.2019 अपराह्न: 1 बजे तक जमा करना होगा।

निविदा प्रपत्र एवम् नियम व शर्तें दिनांक 21.08.2019 को उ0प्र0 की वेबसाइट <https://etender.up.nic.in> पर एवम् विभागीय वेबसाइट www.uppcf.org पर अपलोड कर दी जायेगी। जिसे उपरोक्त वेबसाइट से डाउन लोड किया जा सकता है। निविदा ई-टेन्डरिंग की वेबसाइट <https://etender.up.nic.in> के माध्यम से ही अपलोड की जायेगी जिसमें टेक्निकल विड एवं फाइनेन्शियल विड अलग-अलग होगी।

1- ई-टेन्डर फार्म डाउन लोड करने की अन्तिम तिथि	05.09. 2019	4:00 P.M
2- ई-टेन्डर फार्म अपलोड करने की अन्तिम तिथि	06.09. 2019	1:00 P.M
3- टेक्निकल विड खुलने की तिथि	06.09. 2019	3:00 P.M

ई- टेन्डर निर्धारित दिनांक 06.09.2019 को अपराह्न: 3.00 बजे से पी0सी0एफ0 मुख्यालय के पंचम तल पर खोले जायेगे। निविदा खोलने की तिथि पर अवकाश होने की स्थित में निविदा अगले कार्य दिवस में निर्धारित समय पर खोली जायेगी। निविदाओं को बिना कोई कारण बताये अस्वीकार/विभाजित करने का अधिकार प्रबन्ध निदेशक पी0सी0एफ0 के पास सुरक्षित रहेगा। सशर्त निविदाये स्वीकार नहीं की जायेगी प्रबन्ध निदेशक पी0सी0एफ0 को एक अथवा समस्त निविदाये बिना कारण बताये निरस्त करने का पूर्ण अधिकार सुरक्षित होगा।

ई- टेन्डरिंग के सम्बन्ध में जानकारी प्राप्त किये जाने हेतु कार्यालय के नोडल अधिकारी श्री एस0के0 अग्रवाल ई0डी0पी0 मैनेजर के कार्यालय दूरभाष नं0 0522-2637532 एवम् मो0 नं0 09307059130 पर सम्पर्क किया जा सकता है।


 महा प्रबन्धक (निर्माण)
 पी0सी0एफ0 मुख्यालय।



U.P Cooperative Federation Ltd.

Tender form

TECHNICAL BID


Erenew Money:Rs 39,000/-

Security Money:Rs 1,94800/-

U.P Cooperative Federation Ltd.

TENDER FORM FOR CONSTRUCTION OF NEW MINI TUBEWELL
SIZE 8"x 6" AT PCF COMPOUND 32,Station Road Lucknow.

To,
The Managing Director,
U.P Cooperative Federation Ltd.
32,Station Road Lucknow.



DATED...../...../2019

Dear Sir,

We submit the E-Tender for Construction Of New Mini Tubewell
Size 8"x 6" AT PCF COMPOUND 32,Station Road Lucknow.

Details Regarding me/us tenderer are as under:-

- 1 Name of Tenderer
- 2 Address
- 3 Phone No.
- (a) Office
- (b) Residence
- (c) MobileNo
- (d) Email

4 In case of Partnership firm/ Company /LLP

1.....

Name of all the Partner /Director of company

2.....

Photocopy Of Partnership Deed/ Article Of Association And
Memorandum Of Association The Company/Documents In
Corporation LLP & Registration

3.....

(Certificate Should be annexed)

- 5 GST Number allotted by the
GST Deptt. Of U.P Government (Photocopy enclose)
- 6 PAN number (Photocopy enclose)
- 7 Details of Bank Account For purpose of payment to be
made.(Photocopy enclose)
- 8 Details of (Earnest Money + Tender .Form Cost) Deposit
Bank/Branch
 - (a) Draft/ReceiptNo.
.....
 - (b) Date
.....
 - (c) Amount
.....

All document must be scanned and upload at website
(<https://etender.up.nic.in>)

9 Boaring work Experience in PCF Or other department.

Seal of firm/Company/LLP

Name

Address.....

.....

कराये जाने वाले कार्य से संबंधित निविदा की शर्तें

- 1- समस्त कार्य निर्धारित समय के अन्दर कराये जाने आवश्यक है। कार्य अवधि स्थल हस्तान्तरण की तिथि अथवा स्वीकृति प्राधिकारी द्वारा कार्य प्रारम्भ कराने हेतु लिखित रूप में दी गयी तिथि जो बाद में होगी के आधार पर समयाविधि की गणना की जायेगी।
- 2 - किसी भी कार्य हेतु कोई भी ठेकेदार व्यक्तिगत अथवा फर्म एक से अधिक निविदा नहीं देगा। एक से अधिक निविदा देने पर निविदा निरस्त कर दी जायेगी।
- 3- निविदादाता को सलाह दी जाती है कि वे निविदा भरने से पूर्व कार्य स्थल का निरीक्षण तथा परीक्षण कर लें तथा नजदीकी बाजार कार्य की प्रकृति, भूमि की संरचना, आवागमन आदि के विषय में पूर्णरूप से सुनिश्चित हो लें। प्रत्येक प्रकार की रिस्क, परिस्थितियों एवं अन्य वे सभी तथ्य जो निविदा को प्रभावित करते हों की जानकारी प्राप्त कर लें। निविदा प्रस्तुत करने के बाद इस संबंध में कोई भी क्लेम मान्य नहीं होगा।
- 4- कार्य के लिए निविदा में गवाही उस ठेकेदार द्वारा नहीं दी जायेगी जो उसी कार्य के लिए निविदा दे रहे है। उक्त शर्त पूरी न होने पर ठेकेदार द्वारा दी गयी निविदा निरस्त कर दी जायेगी।
- 5- ई- टेन्डर निर्धारित दिनांक 06-09-2019 को अपरान्ह 3:00 बजे पी0सी0एफ0, मुख्यालय के पंचम तल पर खोले जायेगे।
- 6- उपरोक्त कालम में दर्शायी गयी धरोहर धनराशि रू0 3,9000.00 एवं निविदा फार्म मूल्य रू0 2,360.00 जी0एस0टी0 सहित डी0डी0 ~~बैंक~~ "यू0पी0 कोआपरेटिव फेडरेशन लि0" के पक्ष में एवं लखनऊ में भुगतान योग्य हो, संलग्न करना अनिवार्य है। धरोहर धनराशि एवं निविदा फार्म मूल्य के बिना दी गयी निविदा कदापि स्वीकार नहीं की जायेगी।
- 7- अनुबन्ध करने के पूर्व निविदादाता को कार्य के आगणन के आधार पर गणना करके पूरी सुरक्षा धनराशि का बैंक ड्रापट/ पे आर्डर जो किसी शिड्यूल बैंक का हो तथा यू0पी0 कोआपरेटिव फेडरेशन लि0, के पक्ष में एवं लखनऊ में देय हो, सुरक्षा धनराशि की गणना निम्न अनुसार की जायेगी।
- अ- यदि कार्य की लागत चालिस लाख से अधिक नहीं है तो आगणन धनराशि का 10 प्रतिशत।
- ब- यदि कार्य का लागत चालिस से अधिक है। तो चालिस लाख तक 10 प्रतिशत तथा शेष पर 5 प्रतिशत।
- स- निविदा के साथ जमा की गयी धरोहर धनराशि को अनुबन्ध करते समय सुरक्षा धनराशि जो उपरोक्तानुसार होगी, में समायोजित कर ली जायेगी।
- 8- जमा सुरक्षा धनराशि पर कोई व्याज नहीं देय होगा। कार्य अमानक, समय से न पूर्ण होने अथवा अनुबन्धित प्राविधानों का पालन न करने की स्थित में सुरक्षा धनराशि जब्त कर ली जायेगी।
- 9- कार्य से संबंधित समस्त कर (जी0एस0टी0) आदि जो कार्य से संबंधित देय होंगे, ठेकेदार द्वारा वाहन किये जायेगे। इस संबन्ध में ठेकेदार के किसी भी क्लेम पर पी0सी0एफ0 द्वारा विचार नहीं किया जायेगा।
- 10- कार्य हेतु समस्त टूल्स, पाइप, मोटर पम्प केबल एवं संबधित समस्त सामग्री की व्यवस्था ठेकेदार द्वारा स्वतः करनी होगी कोई भी सामग्री/पार्टस विभाग द्वारा निर्गत नहीं किया जायेगा।
- 11- इस अनुबन्ध के प्रत्येक प्रकरण पर प्रबन्ध निदेशक स्वीकृति प्राधिकारी है तथा उनका निर्णय अन्तिम होगा।
- 12- विभाग किसी भी निविदा को स्वीकृत/ अस्वीकृत कर सकता है जिसका कारण देने की कोई बाध्यता नहीं होगी।
- 13- यू0पी0कोआपरेटिव फेडरेशन लि0 को सभी निविदा अथवा उसका कोई भी भाग स्वीकृति करने का अधिकार सुरक्षित होगा तथा निविदादाता अपनी दी गयी दरों पर कार्य करने को बाध्य होंगे।

- 14- निविदादाता का किसी राष्ट्रीकृत/शिड्यूल् बैंक में खाता होना चाहिये। निविदा प्रपत्र कार्यस्थल/विशिष्टियों निर्माण सामग्री/टूल्स एण्ड प्लांट्स आदि के विषय में पूर्ण जानकारी कर ली है एवं पूर्ण सन्तुष्ट होने के बाद ही निविदा दी है। निविदादाता द्वारा इस नोटिस में अंकित सभी शर्तों को पूर्ण करते हुए अपनी निविदा ई-टेन्डर वेवसाइड पर अपलोड की जायेगी। किसी भी शर्त की अवहेलना होने की स्थिति में निविदा निरस्त कर दी जायेगी।
- 15- निविदादाता द्वारा इस नोटिस में अंकित सभी शर्तों को पूर्ण करते हुए अपनी निविदा ई-टेन्डर वेवसाइड <https://etender.up.nic.in> पर अपलोड की जायेगी। किसी भी शर्त की अवहेलना होने की स्थिति में निविदा निरस्त कर दी जायेगी। सशर्त निविदा कदापि स्वीकार नहीं की जायेगी।
- 16- निविदा स्वीकृति होने की दशा में पी0सी0एफ0 का नाम मात्रिक सदस्य बनना आवश्यक है।
- 17- किसी भी विवाद होने की दशा में रजिस्ट्रार कोआपरेटिव उ0प्र0 लखनऊ आर्बिट्रेटर होंगे। एवम् आर्बिट्रेटर द्वारा दिया गया निर्णय बाध्य होगा।

उपरोक्त निविदाओं की सभी शर्तों से सहमत हूँ।

ठेकेदार/ फर्म का नाम
पता-
हस्ताक्षर-
मुहर-



U.P Cooperative Federation Ltd.

Tender form (Financial Bid)

BILL OF QUANTITY

ESTIMATE FOR CONSTRUCTION OF NEW MINI TUBEWELL AT P.C.F. HEAD QUARTER COMPOUND, LUCKNOW.

PART 'A'

Sl. No.	Description of Work	Qty.	Rate	Amount In Rs
1	2	3	4	5
1.	Transportation of Rig Machine, Compressor & O.P. Unit with their T&P, Diesel, Bits, Tubwell Assembly etc. including loading & unloading complete.	1 Job		
2. Drilling of Tubewell Bore				
(i)	Erection of Rig Machine and its T&P	Job		
(ii)	Dismantling of Rig Machine & its T&P	Job		
(iii)	Drilling of Pilot bore GL to 140 M BGL by 200/250 mm RR bit.	160 m		
(iv)	Reaming of Pilot bore from GL to 80 mts. 600 mm dia and 80 mts. To 140 mts. By 500/550 mm dia RR bit	160 m		
(v)	Laying of Pipe Line for Water arrangement for drilling works	Job		
TOTAL				
3.	Supply of Lalkuan Pea gravel 1.6 to 4.8 mm size	50.00 Cum.		
4. Supply of T.W. Assembly				
(i)	200 mm dia MSER housing pipe blind / Slotted	70.00M		
(ii)	150 mm M.S.Plain pipe	20.00M		
(iii)	150 mm M.S. Slotted Pipe	30.00M		
(iv)	200x150 mm size tube well Accessories complete	1 Set		
(v)	Welding Rod 4.5 mm size	1000 Nos		
TOTAL				
5. Lowering of T.W. Assembly and surrounding of Pea-Gravel				
(i)	Checking, Cleaning and anticorrosive two coat painting of 200/150 mm T.W. assembly	Job		
(ii)	200 mm dia housing pipe from G.L. to 70 MBGL	70.00M		
(iii)	150 mm dia plain/slotted pipe 70 MBGL TO 120.00 MBGL	50.00M		
TOTAL				
6. Development of T.W. by Air-Compressor				
(i)	Erection of Compressor	Job		
(ii)	Dismantling of above	Job		
(iii)	Development by Air-Compressor	50 Hrs.		
TOTAL				
7.	Welding of Well Casing	1 Job		
8.	Logging of Bore hole by electric logger	1 Job		
9.	Erection and dismantling of submersible over pumping plant	1 Job		
10.	Development of T/W by over pumping/ Submersible Pumping plant unit	150 Hrs		
TOTAL				

**ESTIMATE FOR CONSTRUCTION OF NEW MINI TUBEWELL AT P.C.F.
HEAD QUARTER COMPOUND, LUCKNOW.**

PART 'B'

Sl. No.	Description of Work	Qty.	Rate	Amount in Rs
1	2	3	4	5
1.	Pumping Plant. KSB make submersible pump set, capacity 400/500 LPM at 52m delivery Head, 7.5/10 HP suitable for T/W 200x150 mm dia or above, capable of pumping cold and clear water pumping plant and clear water not chemically attacking to pump construction material directly coupled to electric motor 2900 RPM operating on 400 Volts, 3 Phase 50 Hz A.C. supply with bronze impeller and C.I. Non return valve.	1 Set		
2.	Switch Gear & Switch Board. Under this following items will be supplied for 7.5/10 H.P. capacity. 1. L&T make Panel consisting of following : (a) 125 Amp. Capacity MCCB / TPN switch fuse unit 1 No. (b) 100 mm size Ammeture with selector switch 1 No. (c) 100 mm size Voltmeter with selector switch 1 No. (d) K.W. Meter 1 No. (e) Suitable Capacity Power Capacitor 1 No. (f) Single Phase preventor 1 set. (g) Instrumental fuse 3 Nos. 2. 125 Mts. finolex make/submersible cable of suitable size. 3. Earthing connection & necessary power wiring of suitable size from Rebores Tube well to panel switch.	1 No.		
3.	Main Piping & Valve. Under this following items will be supplied i. 52 mtrs 100 mm MSERW 5.4 mm thick double flanges column pipe, in length of 3 mts. long. ii. 1 No. 100 mm C.I. D/F Bend. iii. 1 No. 100 mm A/F Tee. iv. 1 Pair Column Pipe Clamp. v. 1 Set Rubber Packing and necessary nut bolts. vii. 1 No. 100 mm MS D/F pipe in length of 1 mt. Long.	1 Set		
4.	25/32 mm G.I. pipe heavy duty for power connection including socket.	1 Set		
5.	25/32 mm G.I. pipe heavy duty for power connection including socket.	1 Set		
6.	Erection of Pumping Plant	1 Job		
7.	Test of Pumping Plant	1 Job		
8.	Commissioning of Pumping Plant	1 Job		
9.	Power wiring of pumping plant with material & installation of starter & panel etc.	1 Job		
10.	Earthing	1 Job		
		Total		

ESTIMATE FOR CONSTRUCTION OF NEW MINI TUBEWELL AT P.C.F.
HEAD QUARTER COMPOUND, LUCKNOW.

LAYING OF RISING MAIN LINE
PART 'C'

Sl. No.	Description of Work	Qty.	Rate	Amount In Rs
1	2	3	4	5
1.	Supply of 100 mm size GI DF pipe	100 m		
2.	20% For Accessories			
3.	Cutting of Roads for laying of pipe line, cables & of Tubewell including labour & T & P	80 sqm L.S Job		
4.	Laying of 100 m size GIDF / GI Socket pipe	100 m		
5.	Supply & Fiting 100 mm C.I.D.F. Sluice Valve	2 Job		
6.	Nut Bolt & Packing	1 Job		
TOTAL				

ESTIMATE FOR CONSTRUCTION OF NEW MINI TUBEWELL AT P.C.F.
HEAD QUARTER COMPOUND, LUCKNOW.

CONSTRUCTION OF PILLER GURDER
PART 'D'

Sl. No.	Description of Work	Qty.	Rate	Amount In Rs
1	2	3	4	5
1.	Construction of 2 Nos. RCC/RB Pillar for lowering, lifting of Pump Set with MS. Joist Pillar.	1 No.		

Total Rs.

ESTIMATE CONSTRUCTION OF NEW MINI TUBEWELL AT P.C.F.
HEAD QUARTER COMPOUND, LUCKNOW.

ESTIMATE OF CHLORINATION PLANT
PART 'E'

Sl. No.	Description of Work	Qty.	Rate	Amount In Rs
1	2	3	4	5
1.	Supply and Installation of Displacement type chlorination plant of 24 gallon capacity with accessories.	1 No.		

TOTAL Rs.

**ESTIMATE FOR CONSTRUCTION OF NEW MINI TUBEWELL AT P.C.F.
HEAD QUARTER COMPOUND, LUCKNOW.**

PART 'F'- Laying of Cable

Sl. No.	Description of Work	Qty.	Rate	Amount In Rs
1	2	3	4	5
1.	Supply and Laying of 50sqmm Aluminium armoured cable.	100 M		
TOTAL Rs.				

Part Total	Rs.
Part A	
Part B	
Part C	
Part D	
Part E	
Part F	
Grand Total	
GST 12%	
Labour Cess 1%	
GRAND TOTAL	

Seal of firm/Company/LLP

Name

Address

.....

.....